BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

No:EE/YNK-D/E-PMT/03/2019-20 Dated: 18-5-2019

APPROVED TENDER SCHEDULE –'B'

Item-02

Name of Work:-Providing Gym equipments at DEO Marbles in ward No:03

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri.B B UMESHA (SMLP Asphalts)	
				Rate	Rate In Words
1	KSRRB 300-1. Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface levelled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications. MORTH / Chapter 3 Page No. 143 / Item No. 19.1, PWD SR 2018-19	Cum	7.20	230.71	Rupees Two Hundred Thirty and Paise Seventy One Only
2	Providing and fixing pre cast solid cement concrete kerb stones made out of CC 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation ete.,complete Page No. 27 / Item No. 5.30 PWD SR 2018-19	No	80.00	431.40	Rupees Four Hundred Thirty One and Paise Forty Only
3	KSRB 2.8 : Providing and Filling in foundation with granite / trap broken metal 100mm. and down size, with approved sand including hand packing, ramming, watering, including cost of all materials and labour with all lead and lift. complete as per specifications. specification. No. KBS Page No. 7 / Item No. 2.15 of PWD SR 2018-19	Cum	7.20	2568.30	Rupees Two Thousand Five Hundred Sixty Eight and Paise Thirty Only
4	KSRB 14.6-1: Providing and laying heavy duty cobble stones 60mm thick interlock pavers, using cement and course sand for manufacture of blocks of approved size, shape and colour with a minimum compressive strength of 281 kg per sqm over 50mm thick sand bed (average thickness) and compacting with plate vibrator having 3 tons compaction force thereby forcing part of sand underneath to come up in between joints, final compaction of paver surface joints into its final level, including cost of materials, labour and HOM of machineries complete as per specifications. Specification No. KBS. (P.No. 103, I.No. 14.6 of PWD SR 2018-19)	Sqm	72.00	1113.39	Rupees One Thousand One Hundred Thirteen and Paise Thirty Nine Only
5	KSRB 15-19.1 : Providing and applying ready mix priming coat over concrete / masonry / asbestos cement sheet / plastered surfaces including preparing the surface after thoroughly cleaning of oil, grease, dirt and other foreign matter, and sand papering including cost of materials, labour, complete as per specifications. Page No. 124 / Item No. Item No. 15.80, PWD SR 2018-19	Sqm	16.20	39.86	Rupees Thirty Nine and Paise Eighty Six Only

	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri.B B UMESHA (SMLP Asphalts)	
				Rate	Rate in Words
	KSRB 15-19.2 : Providing and applying spray painting in two coats (excluding priming coat) over concrete / masonry / asbestos cement sheet / plastered surfaces with flat wall paint of approved brand to give even shade after cleaning the surface of all dirt, dust and other foreign matter, and sand papering including cost of materials, labour, complete as per specifications.Page No. 124 / Item No. Item No. 15.81, PWD SR 2018-19	Sqm	16.20	91.57	Rupees Ninety One and Paise Fifty Seven Only
7	Supply and fixing of pull down challenger: Metal All tubular steel of 2.50 mm thickness are galvanized and zinc dipped. Joints are Robotic welded. All welded joints are scalloped as neccessary and welded to an approved MIG process. All welds are dressed off removing all sharp edgesand burrs. Zinc primer paint is applied at all the welding points prior to fixing. All metal parts are powder coated using AKZO nobel Great wall powder to the thickness of 80-120 microns. All metals parts are tested in our salt spray machine that uses a 5% Na Cl Solution in accordance to ISO7227 to speed up corrosion for 3000 hrs. Rubber : High quality grip rubber : 1 completely pre assembled equipment modules. Maintenance: Maintain according to EN 16630 EN16630 safety standard with GS test mark. The EN 16630 certificates must be issued by a reputed notified international certifying agency such as IPEMA, TUV CPSC or SGS only. The GS Marks EN16630 certificates must be in the name of tendering pat and not 3rd party. All products must clearly disply the GS mark as has been issued in the EN16630 saftey certificates. Size (1xWxH): 2750x805x2685mm weight :85.4 kg safety Area:6287x4858	Nos	1.00	239400.00	Rupees Two Lakh Thirty Nine Thousand Four Hundred Only
8	Supply and fixing of Seated Chest Press Metal All tubular steel of 2.5 mm thickness are galvanized and zinc dipped. Joints are Robotic welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edgesand burrs. Zinc primer paint is applied at all the welding points prior to fixning. All metal parts are powder coated using AKZO nobel Great wall powder to the thickness of 80-120 microns. All metals parts are tested in our salt spray machine that uses a 5% NaCl Solution in accordance to ISO7227 to speed up corrosion for 3000 hrs. Rubber : High quality grip rubber : 1 completely pre assembled equipment modules. Maintenance: Maintain according to EN 16630 EN16630 safety standard with GS test mark. The EN 16630 certificates must be issued by a reputed notified international certifying agency such as IPEMA, TUV CPSC or SGS only. The GS Marks EN16630 certificates must be in the name of tendering pat and not 3rd party. All products must clearly disply the GS mark as has been issued in the EN16630 saftey certificates. Size (1xWxH): 1955x733x2058mm weight :86.6 kg safety Area:5545x4470	Each	1.00	229425.00	Rupees Two Lakh Twenty Nine Thousand Four Hundred Twenty Five Only

	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri.B B UMESHA (SMLP Asphalts)	
				Rate	Rate in Words
	Supply and fixing of Self Weighted Rower All tubular steel of 2.5 mm thickness are galvanized and zinc dipped. Joints are Robotic welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edgesand burrs. Zinc primer paint is applied at all the welding points prior to fixning. All metal parts are powder coated using AKZO nobel Great wall powder to the thickness of 80-120 microns. All metals parts are tested in our salt spray machine that uses a5% Na Cl Solution in accordance to ISO7227 to speed up corrosion for 3000 hrs. Rubber : High quality grip rubber : 1 completely pre assembled equipment modules. Maintenance: Maintain accoring to EN 16630 EN16630 safety standard with GS test mark. The EN 16630 certificates must be issued by a reputed notified international certifying agency such as IPEMA, TUV CPSC or SGS only. The GS Marks EN16630 certificates must be in the name of tendering pat and not 3rd party. All products must clearly diply the GS mark as has been issued in the EN16630 saftey certificates. Size (1xWxH): 1390x805x1100mm weight :42.4 kg safety Area:3790x3205	Each	1.00	164587.50	Rupees One Lakh Sixty Four Thousand Five Hundred Eighty Seven and Paise Fifty Only
10	Supply and fixing of Elliptical cross Trainer metalAll tubular steel of 2.5 mm thickness are galavnized and zinc dipped. Joints are Robotic welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edgesand burrs. Zinc primer paint is applied at all the welding points prior to fixning. All metal parts are powder coated using AKZO nobel Great wall powder to the thickness of 80-120 microns. All metals parts are tested in our salt spray machine that uses a5% Na Cl Solution in accordance to ISO7227 to speed up corrosion for 3000 hrs. Rubber : High quality grip rubber : 1 completely pre assembled equipment modules. Maintenance: Maintain accoring to EN 16630 EN16630 safety standard with GS test mark. The EN 16630 certificates must be issued by a reputed notified international certifying agency such as IPEMA, TUV CPSC or SGS only. The GS Marks EN16630 certificates must be in the name of tendering pat and not 3rd party. All products must clearly diply the GS mark as has been issued in the EN16630 saftey certificates. Size (1xWxH): 1267x582x1764mm weight :43.5 kg safety Area:4322x3632	each	1.00	139650.00	Rupees One Lakh Thirty Nine Thousand Six Hundred Fifty Only

	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri.B B UMESHA (SMLP Asphalts)	
				Rate	Rate in Words
	Supply and fixing of Rider metal All tubular steel of 2.5 mm thickness are galvanized and zinc dipped. Joints are Robotic welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edgesand burrs. Zinc primer paint is applied at all the welding points prior to fixning. All metal parts are powder coated using AKZO nobel Great wall powder to the thickness of 80-120 microns. All metals parts are tested in our salt spray machine that uses a5% Na Cl Solution in accordance to ISO7227 to speed up corrosion for 3000 hrs. Rubber : High quality grip rubber : 1 completely pre assembled equipment modules. Maintenance: Maintain accoring to EN 16630 EN16630 safety standard with GS test mark. The EN 16630 certificates must be issued by a reputed notified international certifying agency such as IPEMA, TUV CPSC or SGS only. The GS Marks EN16630 certificates must be in the name of tendering pat and not 3rd party. All products must clearly disply the GS mark as has been issued in the EN16630 saftey certificates. Size (1xWxH): 910x655x1270mm weight 29.5 kg safety Area:3310x3000	each	1.00	89775.00	Rupees Eighty Nine Thousand Seven Hundred Seventy Five Only
12	Supply and fixing of Bicycle Metal: All tubular steel of 2.5 mm thickness are galvanized and zinc dipped. Joints are Robotic welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edgesand burrs. Zinc primer paint is applied at all the welding points prior to fixning. All metal parts are powder coated using AKZO nobel Great wall powder to the thickness of 80-120 microns. All metals parts are tested in our salt spray machine that uses a5% Na Cl Solution in accordance to ISO7227 to speed up corrosion for 3000 hrs. Rubber : High quality grip rubber : 1 completely pre assembled equipment modules. Maintenance: Maintain accoring to EN 16630 EN16630 safety standard with GS test mark. The EN 16630 certificates must be issued by a reputed notified international certifying agency such as IPEMA, TUV CPSC or SGS only. The GS Marks EN16630 certificates must be in the name of tendering pat and not 3rd party. All products must clearly disply the GS mark as has been issued in the EN16630 saftey certificates. Size (1xWxH): 1000x498x1290mm weight :51.5 kg safety	Each	1.00	124687.50	Rupees One Lakh Twenty Four Thousand Six Hundred Eighty Seven and Paise Fifty Only

	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri.B B UMESHA (SMLP Asphalts)	
				Rate	Rate in Words
	Supply and fixing of Twist Stepper All tubular steel of 2.5 mm thickness are galvanized and zinc dipped. Joints are Robotic welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edgesand burrs. Zinc primer paint is applied at all the welding points prior to fixning. All metal parts are powder coated using AKZO nobel Great wall powder to the thickness of 80-120 microns. All metals parts are tested in our salt spray machine that uses a5% Na Cl Solution in accordance to ISO7227 to speed up corrosion for 3000 hrs. Rubber : High quality grip rubber : 1 completely pre assembled equipment modules. Maintenance: Maintain according to EN 16630 EN16630 safety standard with GS test mark. The EN 16630 certificates must be issued by a reputed notified international certifying agency such as IPEMA, TUV CPSC or SGS only. The GS Marks EN16630 certificates must be in the name of tendering pat and not 3rd party. All products must clearly disply the GS mark as has been issued in the EN16630 saftey certificates. Size (1xWxH): 1395x650x1750mm weight :39 safety Area 3795x3050 mm	Each	1.00	179550.00	Rupees One Lakh Seventy Nine Thousand Five Hundred Fifty Only
14	Supply and fixing of Big shoulder wheel All tubular steel of 2.5 mm thickness are galvanized and zinc dipped. Joints are Robotic welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edgesand burrs. Zinc primer paint is applied at all the welding points prior to fixning. All metal parts are powder coated using AKZO nobel Great wall powder to the thickness of 80-120 microns. All metals parts are tested in our salt spray machine that uses a5% Na Cl Solution in accordance to ISO7227 to speed up corrosion for 3000 hrs. Rubber : High quality grip rubber : 1 completely pre assembled equipment modules. Maintenance: Maintain accoring to EN 16630 EN16630 safety standard with GS test mark. The EN 16630 certificates must be issued by a reputed notified international certifying agency such as IPEMA, TUV CPSC or SGS only. The GS Marks EN16630 certificates must be in the name of tendering pat and not 3rd party. All products must clearly disply the GS mark as has been issued in the EN16630 saftey certificates. Size (1xWxH): 845x810x1710mm weight :34 kg safety Area 3224x3376	Each	1.00	119700.00	Rupees One Lakh Nineteen Thousand Seven Hundred Only

	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri.B B UMESHA (SMLP Asphalts)	
				Rate	Rate in Words
	Supply and fixing HD Health Walker All tubular steel of 2.5 mm thickness are galvanized and zinc dipped. Joints are Robotic welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edgesand burrs. Zinc primer paint is applied at all the welding points prior to fixning. All metal parts are powder coated using AKZO nobel Great wall powder to the thickness of 80-120 microns. All metals parts are tested in our salt spray machine that uses a5% Na Cl Solution in accordance to ISO7227 to speed up corrosion for 3000 hrs. Rubber : High quality grip rubber : 1 completely pre assembled equipment modules. Maintenance: Maintain accoring to EN 16630 EN16630 safety standard with GS test mark. The EN 16630 certificates must be issued by a reputed notified international certifying agency such as IPEMA, TUV CPSC or SGS only. The GS Marks EN16630 certificates must be in the name of tendering pat and not 3rd party. All products must clearly disply the GS mark as has been issued in the EN16630 saftey certificates. Size (1xWxH): 1065x615x1364mm weight :51 kg safety Area 4090x3555 mm capacity_1 person	Each	1.00	139650.00	Rupees One Lakh Thirty Nine Thousand Six Hundred Fifty Only
16	Supply and fixing HD Squat Pushing Metal: All tubular steel of 2.5 mm thickness are galvanized and zinc dipped. Joints are Robotic welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edgesand burrs. Zinc primer paint is applied at all the welding points prior to fixning. All metal parts are powder coated using AKZO nobel Great wall powder to the thickness of 80-120 microns. All metals parts are tested in our salt spray machine that uses a5% Na Cl Solution in accordance to ISO7227 to speed up corrosion for 3000 hrs. Rubber : High quality grip rubber : 1 completely pre assembled equipment modules. Maintenance: Maintain accoring to EN 16630 EN16630 safety standard with GS test mark. The EN 16630 certificates must be issued by a reputed notified international certifying agency such as IPEMA, TUV CPSC or SGS only. The GS Marks EN16630 certificates must be in the name of tendering pat and not 3rd party. All products must clearly disply the GS mark as has been issued in the EN16630 saftey certificates. Size (1xWxH): 2270x635x1640mm weight :60.2 kg safety Area 5300x3685	Each	1.00	214462.50	Rupees Two Lakh Fourteen Thousand Four Hundred Sixty Two and Paise Fifty Only

	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri.B B UMESHA (SMLP Asphalts)	
				Rate	Rate in Words
	Supply and fixing Mini Ski. Metal: All tubular steel of 2.5 mm thickness are galvanized and zinc dipped. Joints are Robotic welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edgesand burrs. Zinc primer paint is applied at all the welding points prior to fixning. All metal parts are powder coated using AKZO nobel Great wall powder to the thickness of 80-120 microns. All metals parts are tested in our salt spray machine that uses a5% Na Cl Solution in accordance to ISO7227 to speed up corrosion for 3000 hrs. Rubber : High quality grip rubber : 1 completely pre assembled equipment modules. Maintenance: Maintain accoring to EN 16630 EN16630 safety standard with GS test mark. The EN 16630 certificates must be issued by a reputed notified international certifying agency such as IPEMA, TUV CPSC or SGS only. The GS Marks EN16630 certificates must be in the name of tendering pat and not 3rd party. All products must clearly diply the GS mark as has been issued in the EN16630 saftey certificates. Size (1xWxH): 1214x900x1347mm weight :45 kg safety Area 4214x3900	Each	1.00	159600.00	Rupees One Lakh Fifty Nine Thousand Six Hundred Only
18	Supply and fixing of HD Double Health Walker Metal: All tubular steel of 2.5 mm thickness are galvanized and zinc dipped. Joints are Robotic welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edgesand burrs. Zinc primer paint is applied at all the welding points prior to fixing. All metal parts are powder coated using AKZO nobel Great wall powder to the thickness of 80-120 microns. All metals parts are tested in our salt spray machine that uses a5% Na Cl Solution in accordance to ISO7227 to speed up corrosion for 3000 hrs. Rubber : High quality grip rubber : 1 completely pre assembled equipment modules. Maintenance: Maintain accoring to EN 16630 EN16630 safety standard with GS test mark. The EN 16630 certificates must be issued by a reputed notified international certifying agency such as IPEMA, TUV CPSC or SGS only. The GS Marks EN16630 certificates must be in the name of tendering pat and not 3rd party. All products must clearly disply the GS mark as has been issued in the EN16630 saftey certificates. Size (1xWxH): 2015x615x1360mm weight :93 kg safety Area	Each	1.00	239400.00	Rupees Two Lakh Thirty Nine Thousand Four Hundred Only
19	KSRRB 300-1. Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications. MORTH / Chapter 3 Page No. 143 / Item No. 19.1, PWD SR 2018-19	Cum	7.20	230.71	Rupees Two Hundred Thirty and Paise Seventy One Only
20	Providing and fixing pre cast solid cement concrete kerb stones made out of CC 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation ete.,complete Page No. 27 / Item No. 5.30 PWD SR 2018-19	No	80.00	431.40	Rupees Four Hundred Thirty One and Paise Forty Only

	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri.B B UMESHA (SMLP Asphalts)	
				Rate	Rate in Words
	KSRB 2.8 : Providing and Filling in foundation with granite / trap broken metal 100mm. and down size, with approved sand including hand packing, ramming, watering, including cost of all materials and labour with all lead and lift. complete as per specifications. specification. No. KBS Page No. 7 / Item No. 2.15 of PWD SR 2018-19	Cum	43.20	2568.30	Rupees Two Thousand Five Hundred Sixty Eight and Paise Thirty Only
22	KSRB 15-19.1 : Providing and applying ready mix priming coat over concrete / masonry / asbestos cement sheet / plastered surfaces including preparing the surface after thoroughly cleaning of oil, grease, dirt and other foreign matter, and sand papering including cost of materials, labour, complete as per specifications. Page No. 124 / Item No. Item No. 15.80, PWD SR 2018-19	Sqm	12.60	39.86	Rupees Thirty Nine and Paise Eighty Six Only
23	KSRB 15-19.2 : Providing and applying spray painting in two coats (excluding priming coat) over concrete / masonry / asbestos cement sheet / plastered surfaces with flat wall paint of approved brand to give even shade after cleaning the surface of all dirt, dust and other foreign matter, and sand papering including cost of materials, labour, complete as per specifications.Page No. 124 / Item No. Item No. 15.81, PWD SR 2018-19	Sqm	12.60	91.57	Rupees Ninety One and Paise Fifty Seven Only
24	Providing Children play standard Sea Saw Seater Equipment : This equipment is made up of main beam 50mm MS pipe 'A' class of length 98mtr with two handles welded at the ends as a hand are made of 20mm 'A' class pipe. The main beam is pivoted to the bottom supports of 40mm MS pipes by bush bearing clamped by pivot joints which swivel over 28mm dia steel shaft which gets installed in the ground by meas of concrete 2 Nos. seats are made of 250 mm x 200 mm x 18 SWG MS sheets with T hand rest at the front. Air pipe are if ISI grade. All the pipes are painted with two coats of super set paint over a coat of protective Zinc chromate yellow oxide including fixing the play equipments in CC 1:2:4, curing etc., complete with all lead, lift, loading, unloading and any other incidental charges and as perthe draing and specification and direction of the engineer in charge of the work.	Each	1.00	27930.00	Rupees Twenty Seven Thousand Nine Hundred Thirty Only
25	Providing Children play Merry-go-Round equipment : Made of MS 'A' Class pipes. Main pillars in 100 mm dia fitted with shaft and two bearing the other cross members are in 25 & 20 mm MS A Class pipe the bottom ring is made out of 25mm of ring size is 1.20 mts dia fitted with four seats are in mental sats if 250 x 200 x 18 SWG handles are made out of 20mm NB pipes and othe supports are in 25mm MS 'A' Class pipes. All the pipes are painted with two coats of super set paint over a coat of protective Zinc chromate yellow oxide including fixing the play equipments in CC 1:2:4, curing etc., complete with all lead, lift, loading, unloading and any other incidental charges and as perthe draing and specification and direction of the engineer in charge of the work.	Each	1.00	27930.00	Rupees Twenty Seven Thousand Nine Hundred Thirty Only

	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri.B B UMESHA (SMLP Asphalts)	
				Rate	Rate in Words
26	Providing Children Play 2 - Seater Swing : This Swing consosts of 2 Nos, seat of solid fibbed FP of size 480 mm x 180 mm x 3.5 mm supported by MS chains. The chains are supported by circular housing with bearing from which the chain in suspended. The main beam is of 50 mm MS 'A' class pipe Size of MS chain 30 mm x 20 mm x 5mm thick The 2 Nos inverted 'V' beams are of 50 mm 'A' class pipes secured at the top the main beam by means of CI castings (Heavy duty for elders) All pipes are of ISI grade all the pipes are painted with two coats of super set paitng over a coat of protective Zinc chromate yellow oxide including fixing the play equipments in CC 1:2:4, curing etc., complete with all lead, lift, loading, unloading and any other incidental charges and as perthe draing and specification and direction of the engineer in charge of the work.	Each	1.00	45885.00	Rupees Forty Five Thousand Eight Hundred Eighty Five Only
27	Providing Children Play Standard Swing : This Swing consosts of 2 Nos, seat of solid fibbed FP of size 480 mm x 180 mm x 3.5 mm supported by MS chains. The chains are supported by circular housing with bearing from which the chain in suspended. The main beam is of 50 mm MS 'A' class pipe Size of MS chain 30 mm x 20 mm x 5mm thick The 2 Nos inverted 'V' beams are of 50 mm 'A' class pipes secured at the top the main beam by means of CI castings (Heavy duty for elders) All pipes are of ISI grade all the pipes are painted with two coats of super set paitng over a coat of protective Zinc chromate yellow oxide including fixing the play equipments in CC 1:2:4, curing etc., complete with all lead, lift, loading, unloading and any other incidental charges and as perthe draing and specification and direction of the engineer in charge of the work.	Each	1.00	55860.00	Rupees Fifty Five Thousand Eight Hundred Sixty Only
28	Duck wheel	Each	1.00	67830.00	Rupees Sixty Seven Thousand Eight Hundred Thirty Only
29	Duck Swing (2 seater)	Each	1.00	55860.00	Rupees Fifty Five Thousand Eight Hundred Sixty Only
30	FRP Mini Slide	Each	1.00	22942.50	Rupees Twenty Two Thousand Nine Hundred Forty Two and Paise Fifty Only
31	Mini Slide	Each	2.00	15960.00	Rupees Fifteen Thousand Nine Hundred Sixty Only

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.